

CLAIMS

1. A method for powering up an optical network,
comprising the steps of:

(a) selecting an optical link between a transmitter
5 and a receiver in the optical network, the optical link being
divided into a number of sections by monitoring points located
between the transmitter and the receiver;

(b) selecting a first section of the optical link
nearest to the transmitter in the optical network;

10 (c) gradually increasing optical power of an optical
signal provided to the selected section of the optical link
from the transmitter until the optical signal is detected at
the monitoring point belonging to the selected section;

(d) verifying if the detected optical signal is
15 being detected at a correct location according to a network
specification and if the power of the detected optical signal
is at the expected level according to the network
specification;

(e) selecting a next section of the optical link
20 adjacent to the previously selected section and further away
from the transmitter in the optical network; and

(f) repeating the steps (c) to (e) until all
sections in the optical link have been selected.

2. A method as described in claim 1, wherein the step
25 (a) of selecting an optical link comprises selecting an

optical link that has one section and one first monitoring point located at the receiver.

3. A method as described in claim 1, wherein the step (c) of gradually increasing the optical power comprises
5 increasing the optical power continuously.

4. A method as described in claim 1, wherein the step (c) of gradually increasing optical power comprises decreasing attenuation of attenuators in the optical network.

5. A method as described in claim 1, further comprising
10 the step of setting attenuation of attenuators and gain settings of amplifiers in the selected section, the step being performed after the step (d) of verifying.

6. A method as described in claim 5, wherein the step (c) of gradually increasing optical power comprises increasing
15 the optical power in steps provided by sets of precalculated link budgets.

7. A method as described in claim 1, wherein the step (c) of gradually increasing optical power comprises detecting the optical signal at the monitoring point by detecting a
20 dither tone modulated onto the signal.

8. A method as described in claim 1, further comprising the step of reconnecting the selected section of the optical link according to the network specification, if the step (d) of verifying gives the results that the detected optical
25 signal is not being detected at the correct location.

9. A method as described in claim 1, the method being performed on a pre-existing optical network so that pre-existing signals on the network are not being disturbed.

10. A method as described in claim 9, the method being performed such that pre-existing amplifier gain settings are not being changed.

11. A method as described in claim 1, the method being performed on the link in the optical network remotely.

12. A system for powering up an optical network,
10 comprising:

(a) means for selecting an optical link between a transmitter and a receiver in the optical network, the optical link being divided into a number of sections by monitoring points located between the transmitter and the receiver;

15 (b) means for selecting a first section of the optical link nearest to the transmitter in the optical network;

(c) means for gradually increasing optical power of an optical signal provided to the selected section of the optical link from the transmitter until the optical signal is detected at the monitoring point belonging to the selected section;

(d) means for verifying if the detected optical signal is being detected at a correct location according to a network specification and if the power of the detected optical signal is at the expected level according to the network specification;

(e) means for selecting a next section of the optical link adjacent to the previously selected section and further away from the transmitter in the optical network; and

(f) means for repeating the steps (c) to (e) until
5 all sections in the optical link have been selected.

13. A system as described in claim 12, wherein the means (c) for gradually increasing optical power comprises means for gradually increasing the optical power in steps provided by sets of precalculated link budgets.

10